



Town of Mendon
2282 U.S. Route 4
Mendon, Vermont 05701
802-775-1662
www.mendonvt.org

July 3, 2018

REQUEST FOR BIDS
Town of Mendon, VT
Culvert 07-56 Replacement and Ditchwork

The Town of Mendon is accepting proposals for TH#7 Wheelerville Road Erosion Control Project. The project length is approximately 630 feet located on Wheelerville Road between culverts 07-27 and 07-55.

The Contractor must have workman's compensation and insurance.

Beginning at culvert 07-57:

- Reset inlet side of culvert 07-57 by removing approximately 5' of gravel of either side of the culvert and underneath to lower it down in the channel and backfill. Reset stone headwall.
- Create U shaped ditches along the west side of the road for 360 feet to culvert 07-56. Seed and Mulch.
- Taper edge of the roadway along the east side of road for 360' to culvert 07-56. Seed and Mulch.
- Replace culvert 07-56 with 24" X 30' plastic culvert. The culvert will be supplied by the Town. Stone headwalls to be constructed at the inlet and outlet.
- Install stone lined U shaped ditches with 10-12" stone for 245' on west side of the road from culvert 07-56 to culvert 07-55. Remove large rock currently located in the ditchline. Do not disturb functioning underdrain in this location.
- Remove berm 254' on east side of road from culvert 07-56 to culvert 07-55. Remove clump of three trees located in the ditchline. Install stone lined U shaped ditches with 10-12" stone for 140' to the water turnout. Stone line the water turnout. Taper bank from the turn out to culvert 07-56.
- The road should remain open through construction and provide flagging and signage in accordance with the MUTCD.
-
- Construction timeline is expected to be completed within 5 working days Mon.-Fri. unless otherwise arranged with the town.
- Construction must be complete by September 30, 2018.

A site visit will be held on Tuesday, July 17, 2018 at 8:30 AM at the project location identified by yellow construction tape. Bids are due at the Town Office on Monday July 23, 2018 at 12:00 PM. Please refer questions to Bill Ellis, Road Commissioner at 802-773-4402 or Sara Tully, Mendon Town Administrator at 802-775-1662 or mendonadmin@comcast.net.

REQUEST FOR BIDS
Town of Mendon, VT
Culvert 07-56 Replacement and Ditchwork

The Town of Mendon is requesting bids from qualified contractors to establish ditches and install a 24" X 30' culvert. A detailed Request for Bids can be found posted www.mendonvt.org. A site visit to be held at the project location on Wheelerville Road July 17, 2018 at 8:30 AM. Bids shall be delivered to the Mendon Town Office no later than July 23, 2018 at 12:00 PM. Proposals submitted later than this date and time will not be opened, and will be rejected.